

Site-Readiness Check Guide

LUA BIM LABS Starter - Track 7 Quick Reference | Track completion card - Day 54

What Site Teams Need from BIM

Output	Format	Purpose
Coordination Drawings	A1/A3 prints, PDF	Shows MEP routing with confirmed elevations and grid references for each zone
Setting-Out Data	Dimension tables, grid-referenced drawings	Marks hole positions, hanger spacings, and equipment base locations on slab or wall
Model Access (Viewer)	NWD file, Autodesk Viewer link, BIM 360 Docs	Site supervisors navigate 3D model to understand spatial relationships
Clash Clearance Sign-off	Written memo or tracker export	Confirms all Critical and Major clashes in the zone are resolved before work starts
Spool Drawings	ISO drawings (isometric), spool delivery schedule	Pre-fabricated assemblies matched to site by unique spool ID tag
RFI Response	Written RFI response (within 24 hours)	Formal resolution when site conditions differ from model or drawings

RFI Process Flow

...

Site condition differs from model or drawing

v

Site supervisor raises formal RFI
(Assigned RFI number, description, photo)

v

RFI submitted to BIM Coordinator / Engineer

v

BIM Coordinator / Engineer reviews model + site info

v

Response issued within agreed timeframe (typically 24-48 hours)

v

If model change required:

-> Model updated, drawings reissued at new revision

v

RFI closed with reference to resolution in issue tracker

v

Deviation captured in as-built record if site differs from revised model

...

As-Built Update Checklist

- When installation deviates from the BIM model:
- [v] Deviation identified and described (element, location, nature of change)
 - [v] RFI raised and formally responded to
 - [v] BIM modeler updates the model to reflect actual installed position
 - [v] Updated model version saved with "AS-BUILT" in the file name

- [V] Revised coordination drawing issued at a new revision
- [V] Site team notified of updated drawing and old revision superseded
- [V] Deviation logged in the project change register

Spool Drawing Basics

Term	Meaning
Spool	Pre-built section of pipework or ductwork (with fittings, flanges, supports) - manufactured off-site
ISO Drawing	Isometric view spool drawing showing 3D routing, all connections, and dimensions
Cut Length	Exact length of each straight pipe segment, accounting for fitting allowances
Spool ID	Unique tag on each spool matching the spool drawing - site installs by matching tag to drawing
End Preparation	Type of joint at each spool end (flanged, grooved, butt-welded)
BIM-to-Fabrication	Model must be at LOD 350, clash-resolved, before spool drawings are generated

Common Site-to-BIM Feedback Types

Feedback Type	Typical Cause	BIM Response
Slab deviation	Floor poured out of level - not as modeled	Survey actual level, adjust model elevation, reissue coordination drawing
Structure out of position	Column or beam installed offset from design	RFI to structural engineer, update model if accepted, recheck clashes
Service omitted from model	Design change issued to site but not captured in BIM	Model update required, all affected coordination drawings reissued
Insufficient clearance on site	Void tighter than modeled due to finishes thickness	Check finish build-up, adjust model with confirmed data, re-coordinate
Fitting not available (procurement)	Specified fitting type unavailable or substituted	Engineer approval for substitution, model updated with alternate family